

# STORAGE BUILDINGS 12' - 30' W

STATES: AR, OK, MO, NE, IL, IN, IA, KS

NON CERTIFIED



Regular Style



Boxed Eave Style



Vertical Roof Style

## 12' WIDE—24' WIDE STORAGE BUILDINGS

<u>12x30x8</u> \$6,095	<u>18x30x8</u> \$6,872	<u>20x30x8</u> \$7,280	<u>22x30x8</u> \$7,910	<u>24x30x8</u> \$8,461	<u>12x30x8</u> \$6,330	<u>18x30x8</u> \$7,107	<u>20x30x8</u> \$7,515	<u>22x30x8</u> \$8,155	<u>24x30x8</u> \$8,696	<u>12x30x8</u> \$7,085	<u>18x30x8</u> \$8,037	<u>20x30x8</u> \$8,380	<u>22x30x8</u> \$9,020	<u>24x30x8</u> \$9,611
<u>12x35x8</u> \$6,526	<u>18x35x8</u> \$7,368	<u>20x35x8</u> \$7,781	<u>22x35x8</u> \$8,481	<u>24x35x8</u> \$9,037	<u>12x35x8</u> \$6,781	<u>18x35x8</u> \$7,613	<u>20x35x8</u> \$8,031	<u>22x35x8</u> \$8,751	<u>24x35x8</u> \$9,287	<u>12x35x8</u> \$7,651	<u>18x35x8</u> \$8,708	<u>20x35x8</u> \$9,076	<u>22x35x8</u> \$9,766	<u>24x35x8</u> \$10,387
<u>12x40x8</u> \$6,866	<u>18x40x8</u> \$7,783	<u>20x40x8</u> \$8,231	<u>22x40x8</u> \$9,006	<u>24x40x8</u> \$9,567	<u>12x40x8</u> \$7,151	<u>18x40x8</u> \$8,023	<u>20x40x8</u> \$8,491	<u>22x40x8</u> \$9,286	<u>24x40x8</u> \$9,827	<u>12x40x8</u> \$8,126	<u>18x40x8</u> \$9,283	<u>20x40x8</u> \$9,696	<u>22x40x8</u> \$10,461	<u>24x40x8</u> \$11,112
NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.					NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.					NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.				
ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END					ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END					ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END				
REGULAR STYLE HAS 6" ROOF OVERHANG ON FRONT AND BACK.					BOXED EAVE HAS 6" ROOF OVERHANG ON FRONT, BACK AND SIDE EAVES.					VERTICAL ROOF HAS NO OVERHANG ON FRONT OR BACK JUST ON SIDE EAVES.				

## 26' WIDE—30' WIDE STORAGE BUILDINGS

<u>26x30x8</u> \$10,045	<u>26x35x8</u> \$10,906	<u>26x40x8</u> \$11,451	<u>26x30x8</u> \$10,195	<u>26x35x8</u> \$11,106	<u>26x40x8</u> \$11,651	<u>26x30x8</u> \$11,110	<u>26x35x8</u> \$12,196	<u>26x40x8</u> \$12,916
<u>28x30x8</u> \$10,455	<u>28x35x8</u> \$11,431	<u>28x40x8</u> \$11,976	<u>28x30x8</u> \$10,605	<u>28x35x8</u> \$11,631	<u>28x40x8</u> \$12,176	<u>28x30x8</u> \$11,520	<u>28x35x8</u> \$12,721	<u>28x40x8</u> \$13,441
<u>30x30x8</u> \$10,865	<u>30x35x8</u> \$11,956	<u>30x40x8</u> \$12,501	<u>30x30x8</u> \$11,015	<u>30x35x8</u> \$12,156	<u>30x40x8</u> \$12,701	<u>30x30x8</u> \$11,930	<u>30x35x8</u> \$13,246	<u>30x40x8</u> \$13,966
NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.			NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.			NOTE: BASE RAIL FRAME LENGTH'S ARE 20',25',30' ETC.		
ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END			ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END			ALL SIZES INCLUDE 1-8"WX7'H ON SIDE, 1-36"X80" MAN DOOR ON END, 1-24"X36" WINDOW ON END		
REGULAR STYLE HAS 6" ROOF OVERHANG ON FRONT AND BACK.			BOXED EAVE HAS 6" ROOF OVERHANG ON FRONT, BACK AND SIDE EAVES.			VERTICAL ROOF HAS NO OVERHANG ON FRONT OR BACK JUST ON SIDE EAVES.		

### STANDARD FEATURES:

14 Gauge frame, 6ft Std legs, 29 Gauge roofing, maximum rafter/column spacing 5' on center or less, braces on all center rafters and on top corner posts, 4ft welded truss on 22'-24' ft wide carports. 16ft welded trusses on 26'-30' wide carports. roofing, maximum rafter/column spacing 4' on center or less, braces on all top corner posts, Single leg system for buildings 6'-12' tall, double leg system for building 13'-16' ft tall legs.  
Customer must supply lull lift for buildings 13'-16' tall leg height.



- Free Installation On Your Level Lot
- Financing Available / Rent To Own Available
- Engineer Plans Available Call 877-494-2997
- Rebar Anchors Included /Concrete Anchors Included

"ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE"

©2024 Copyright All Rights Reserved Tri State Carports, Inc 2024 V3

# STORAGE BUILDINGS 12'-30' WIDE OPTIONS

12 GAUGE FRAME UPGRADE	12'-18'W	\$750	\$800	\$850	We strongly recommend you to purchase vertical roofs on buildings 31ft or longer to prevent leaks.	*30 Day Workmanship warranty on all Buildings, effective day of Installation. *20 Year limited warranty on 12 Gauge framing materials assuming regular care and maintenance given to building.						
	20'-24'W	\$1,030	\$1,140	\$1,240								
	26'W-30'W	\$1,105	\$1,215	\$1,315								
3FT BRACE UPGRADE 12'-24'W		\$101	\$115	\$130	3' brace upgrade recommended for buildings 8' and higher. Extra support recommended for buildings 10'-12' Tall Legs to	<b>12'-24' wide buildings 10ft storage</b> Over all length of side wall storage enclosure.						
3FT BRACE UPGRADE 26'-30'W		\$128	\$144	\$160								
MOBILE HOME ANCHORS		\$240	\$300	\$300								
Labor Fees	30'L	35'L	40'L	<b>CLOSE ONE END (PER END)</b>								
				12'W	18'W	20'W	22'W	24'W	26'W	28'W	30'W	
Build over fee	\$300	\$350	\$400	8'H	\$750	\$916	\$980	\$1,075	\$1,243	\$1,430	\$1,545	\$1,660
Cut leg fee	\$250	\$300	\$350	Vertical end add on (per end)	\$300	\$370	\$392	\$430	\$498	\$572	\$618	\$664
<b>ROOF REFLECTIVE INSULATION ADD ON:</b> Add 2' to width and multiply by length. EX. 12' wide x 21' long (14x21= 294 sf x 2.50 = \$ 735.00) R Value 14.7 95% Reflectivity Helps reduce building condensation	<b>REFLECTIVE INSULATION (BOTH SIDES) ADD ON:</b> Multiply leg height by length by 2. EX. 21' long x 6' tall 6x21= 126 sf x 2 =252 sf x 2.50 = \$630.00 both sides											
	<b>REFLECTIVE INSULATION (PER END) ADD ON:</b> Add 3' to leg height multiply by width EX. 12' wide x 6' tall 9x12= 108 sf x 2.50= \$270.00 per end											
	Add \$100.00 Trip Fee on any purchase less than \$500.00			Connection fees valid only if you are purchasing 2 buildings at the same time (not on existing buildings)				Connecting end to end. \$100.00 Connecting side to side. \$150.00				

<b>EXTRA FRAME BOW</b>	<b>WELDED TRUSSES</b>	<b>EXTRA BRACES</b>	<b>GARAGE DOORS</b>	<b>*GABLE END</b>
12'-20' WIDE \$252 EA. 22'-24' WIDE \$312 EA. 26'-30' WIDE \$346 EA. ADD \$15.00 FOR EACH ADDITIONAL HEIGHT.	4' LONG \$32.00 EA. 5' LONG \$50.00 EA. 8' LONG \$94.00 EA.	2' LONG \$14.00 EA. 3' LONG \$22.00 EA.	6'WX6'H \$704.00 EA. 8'WX7'H \$848.00 EA. 9'WX7'H \$920.00 EA. 10'WX8'H \$992.00 EA. 10'WX10'H \$1,064.00 EA. 12'WX12'H \$2,304.00 EA.	12'-20' WIDE \$288.00 EA. 22'-24' WIDE \$396.00 EA. 26'-30' WIDE \$432.00 EA.
<b>MOBILE HOME ANCHORS</b>	<b>ASPHALT ANCHORS</b>	<b>WINDOWS white with grids</b>		<b>**EXTENDED GABLE</b>
3/4"X30" \$30.00 EA.	3/4"X30" \$30.00 EA.	24"X36" \$190.00 EA.		12'-20' WIDE \$504.00 EA. 22'-24' WIDE \$540.00 EA. 26'-30' WIDE \$792.00 EA.
<b>WALK IN DOOR left outswing</b>	<b>EXTRA PANELS 36" wide</b>			
36"X80" \$515.00 EA. ADD \$50.00 SIDE FEE (IF FRAME HEADER BAR IS NEEDED ADD \$100) <u>BUILDING MUST BE A MIN OF 7FT TALL TO INSTALL DOOR ON SIDE.</u>	21' LONG \$130.00 EA. 26' LONG \$158.00 EA. 31' LONG \$187.00 EA.	*36' LONG \$216.00 EA. *41' LONG \$259.00 EA. *NOT A CONTINUOUS PANEL.	ADD \$100.00 SIDE DOOR FEE (PER EACH DOOR) <u>BUILDING MUST BE 1' TALLER TO INSTALL DOOR ON SIDE.</u> ELECTRIC DOOR OPENER \$950.00 EACH	
<b>EXTRA L TRIM</b>	<b>EXTRA J TRIM</b>	<b>45° TRIM KIT</b>	<b>RECOMMENDED 10-12' TALL ON CONCRETE OR GROUND.</b>	<b>EXTRA SUPPORTS \$100.00 EACH</b>
\$1.25 (PER FT)	\$1.12 (PER FT)	\$99.00 EA. MUST CLOSE END OR SIDE FIRST.		



**CONCRETE DIMENSIONS**  
 In reference to frame size  
 Ex. 12'Wx30'L building frame size. Make pad 12'8"Wx30'8"L. Make the extra 4" all around slope away from the building edge to run off water.

<b>FRAME OUTS</b>	<b>WINDOW \$80.00 EACH</b>	<b>WALK DOOR \$90.00 EACH</b>	<b>DOOR FRAME OUTS</b>	6'W-12'W ON END <u>\$150.00 EACH</u> 13'W-16'W ON END <u>\$300.00 EACH</u>	6'W-12'W ON SIDE <u>\$200.00 EACH</u> 13'W-16'W ON SIDE <u>\$400.00 EACH</u>	ON ENDS: MUST CLOSE FIRST FOR FRAME OUTS, IF NO PANELS WANTED ON END (FRAME END ONLY) <u>DISCOUNT 20% FROM CLOSED END PRICE.</u>
<b>16FT WIDE MAX ON END AND SIDE DOOR OPENINGS</b>						



2 Under Ground